

## Waterberging Achterberg West

Type verharding	Oppervlakte	verhard [%]	verhard opp
Verharding - Rijbaan	4.668 m2	100%	4.668 m2
Open verharding - Haaksparkeren	1.238 m2	100%	1.238 m2
Open verharding - Langsparkeren	426 m2	100%	426 m2
Verharding - Trottoir	3.650 m2	100%	3.650 m2
Kavel - Vrijstaande woning	8.973 m2	70%	6.281 m2
Kavel - Hoekwoning	4.974 m2	80%	3.979 m2
Kavel - Rijwoning	9.168 m2	90%	8.251 m2
Kavel - Appartementen	1.575 m2	100%	1.575 m2
<b>Totaal</b>	<b>34.672 m2</b>		<b>30.069 m2</b>

78 mm T100+10%  
 2345 m3  
 0,5 m1 bergingsdiepte  
 4691 m2 opp. Wadi  
 0,47 ha opp. Wadi  
 4,96 ha opp. Project  
 9,46 % perc. Project

Wadi 1	3390 m2	1695 m3	60%	72%
Watergang 1	375 m2	187,5 m3	7%	8%
Watergang 2	352 m2	176 m3	7%	8%
Wadi 2	1280 m2	640 m3	27%	27%
<b>Totaal</b>	<b>5632,42 m2</b>	<b>2698,5 m3</b>		
	142%	115%		
<i>Overschot</i>		<i>353 m3</i>		